



10708 NE 2ND AVE.
PORTLAND, OREGON 97211
(503) 289-9204
(503) 289-0305 Fax
CCB #52938

Proposal

Date 04/20/26

To: Norwest Contractors
7235 SW Stephen Ln
Portland, OR 97225

Phone (503) 291-6986

Attention	: David Horan	Project Id	: 10738
Project Desc.	: NW Windermere TI- CD Set	Ship Via	: Installed by F&S
Terms	: n/a	P.O. Number	: n/a
Delivery Date	: n/a	Estimator	: Evan Ramsey

Description	Qty	Unit	Price
PROJECT: NW Windermere TI Bid Documents: IFC Set Architect: TVA Drawings Dated: 4/10/26 Revs: Rev. 3 04/13/26			
Office 214,215,220,221-PLAM C-TOP & Shelving	4	rooms	\$ 11,772.00
Office 232,239,240-PLAM C-TOP & Shelving	3	room	\$ 7,146.00
Office 216,217,218,219,223-PLAM C-TOP & Shelving	5	rooms	\$ 8,780.00
Office 222-PLAM C-TOP & Shelving	1	room	\$ 3,529.00
Office 224-PLAM C-TOP & Shelving	1	room	\$ 4,447.00
Office 225-PLAM C-TOP & Shelving	1	room	\$ 1,723.00
Work Area 237 Casework & QTZ C-Top	1	area	\$ 9,581.00
Work Area 237 Island Casework & QTZ C-Top	1	area	\$ 3,813.00
Waiting-Reception Desk & QTZ C-Top	1	area	\$ 13,557.00
Kitchen 227-Casework & QTZ C-Top	1	area	\$ 6,455.00
Kitchen 227- Island Casework & QTZ C-Top	1	area	\$ 7,794.00
Conference 213- Casework & QTZ C-Top	1	area	\$ 1,384.00
Waiting 212 Beverage Station & QTZ C-Top	1	area	\$ 807.00
Waiting 212- Veneer Wall Panel & Casework	1	area	\$ 5,399.00
Store 210 Shelving - Veneer Shelving	1	area	\$ 4,320.00
Qtz- Supply & Install	1	job	\$ 23,350.00
Delivery & Installation	1	job	\$ 4,300.00
Base Bid	1		\$ 118,157.00
TOTAL			\$ <u>118,157.00</u>

Alternates / Exclusions / Clarifications

EXCLUSIONS

Unless explicitly noted in the proposal, the following items are excluded from Form & Structure's scope of work:

All demolition work.

Any item shown in plan view but not dimensioned, detailed, or called out in elevations.

Site finishing, including painting, patching, and putty work.

Phased delivery or installation beyond a single mobilization.

Mock-ups or material samples beyond standard submittals.

Installation labor performed at prevailing wage rates unless explicitly included in the proposal.

Description	Qty	Unit	Price
-------------	-----	------	-------

LEED documentation or AWI certification (unless otherwise noted).
Supply and installation of the following:
FRP panels, plastic laminate wainscot, wall protection, chair rail, or bumper rail.
Glass, glazing tracks, or glass hardware.
Metal or plastic corner guards.
Metalwork, metal fabrications, or plastic fabrications not integrated into casework.
Rubber base at casework toe spaces.
Appliances, plumbing fixtures, or electrical fixtures.

CLARIFICATIONS:

GENERAL TERMS:

F&S reserves the right to adjust prices 30 days after the original bid date.
All quoted material and hardware pricing is based on availability and costs at the time of bid.
F&S reserves the right to adjust pricing due to unforeseen increases at time of ordering;
any changes will require written approval via change order prior to procurement.
All work will be performed during standard working hours unless otherwise agreed upon.
F&S maintains standard commercial liability and workers' compensation coverage.

WARRANTY AND FABRICATION:

Standard warranty is one (1) year, written or implied, unless otherwise stated in the proposal or contract.
Casework is constructed using dowel-and-screw joinery per industry standards.
Dovetail joinery or other premium construction methods are not included unless specifically requested.
Standard finish consists of one coat of sanding sealer and two coats of clear lacquer.

FINISH MATERIALS:

If finish schedule is not available at the time of bid, plastic laminate pricing is based on mfg's standard colors and patterns.
A maximum of four (4) plastic laminate colors is included per project. Additional colors may result in upcharges.
If specified P-Lam, PVC, ABS, or T-Mold edgebanding is not readily available or requires a minimum order,
additional charges will apply.

HARDWARE ASSUMPTIONS:

Hinges: Blum 125° concealed, self-closing, no magnetic catches
Pulls: Brushed chrome standard pulls
Drawer Slides: Accuride 3832 full-extension slides
Adjustable Shelving: 5mm hole system with KV nickel spoon supports
In-wall support brackets are to be furnished by F&S but installed by the general contractor.
F&S is not responsible for manufacturer lead times for specialty items

FABRICATION NOTE:

Unless otherwise agreed upon in writing, all casework will be fabricated using dowel-and-screw construction,
which meets or exceeds typical performance requirements. While some projects may be spec'd at AWI Custom Grade,
fabrication will follow our standard construction methods unless explicitly required and priced accordingly.

Please Note: Prices valid for 30 days.

Authorized Signature